

**Proposed Works**

**General Scope:**

- A Fabric to Waiting Area wall to be selected by A. I. B.
- B Feature timber frame detail to floor and ceiling in American Walnut.
- C Feature stud partition, one skin ply, with recess for signage panel.
- D Free standing timber slatted screen from floor to ceiling - American Walnut.
- E 3 compartment perimeter trunking with power and data.
- F New timber door - fire rated with vision panel with new stud partition around.
- G New S/S handrail - refit carpet from Banking Hall to stairs and landing with new nosings.
- H Construct 100mm stud partition - provide power within ceiling void.
- I Glass partition with full height frameless glass door.
- J 100mm sliding folding partition to laminate floor with acoustic baffles to ceiling void.
- K Slab to slab 100mm PB partition to paint finish.
- L Supply and install secondary glazing to office windows.
- M Supply and lay new carpet - Interface "Hot Pink" to open plan with "Insomnia" to waiting area.
- N Construct new top detail over existing base in 18mm M. D. F. finished in white satin wood.
- O Supply and install new 600 x 600mm suspended ceiling with white 25mm grid and white dune lay-in tiles, fit new louver grills over existing a/c outlets.
- P Decoration to walls and partitions matt emulsion finish. Colour to be confirmed.

